

Name of work: Maintenance of toilet (present girls hostel) at Ura Central School

Sub:Bill of Quantities

Sl.No	Particulars	Qty	Units	Rate in words	Rate in Figure	Amount
1	Demolishing cement concrete 1:3:6 & richer, including disposal of materials within 50m lead	23.55	cum			
2	Taking out doors, windows and clerestory window shutters >3sq.m (steel or wood) including stacking within 50m lead	23.00	each			
3	Dismantling old plaster or skirting, raking out joints and cleaning the surface for plaster including disposal of rubbish within 50m lead. Wash basin	56.57	sq.m			
4	Dismantling of flushing cistern/Indaian type WC of any size including stacking of useful materials & disposal of rubbish within 50 m lead	10.00	Nos			
5	Providing & fixing white/ coloured Glazed tiles, 150 x 150 mm in skirting, step risers, dado, finished with flush pointing in white cement.	29.00	sq.m			
6	Providing and laying in position plain cement concrete excluding the cost of centering and shuttering - All work upto plinth level. 1:2:4 (1 cement : 2 sand : 4 graded crushed rock 20 mm nominal size)	16.08	cum			
7	Providing & laying 20mm cement plaster. C.M 1:4	56.57	sq.m			
8	Providing and fixing wash basin connection pipe for steel basin	12.00	each			
9	Providing & fixing in position dressed wood work in frames of doors, windows, clerestory windows and other frames, wrought and framed Mixed Conifer. Door V/F	0.75	cum			

10	Providing & fixing battened and block door shutters, Mixed Conifer including the cost of hinges 38mm	59.24	sq.m			
11	Providing & applying one coat of primers Cement primer	230.60	sq.m			
12	Providing and applying wood stains, varnishes & polishes Synthetic varnish (clear) - two coats, including coat of wood filler on new work	89.63	sq.m			
13	Providing & applying one coat of primers Red lead primer	169.40	sqm			
14	Providing and applying finishing coats Green corrugal, ready mixed on G.I. sheets, two coats on new work	169.40	sqm			
15	Providing & fixing Indian-type vitreous china w.c squatting pan, including 100 mm H.C.I.P or S trap, 10 lit low level vitreous china cistern & fittings, repair walls 500mm, white	10.00	Each			
16	Providing & fixing G.I. pipes including G.I. fittings & clamps & repair walls. 15mm	20.00	m			
	20mm	20.00	m			
17	Providing & fixing brass bibcock 15mm, brass	38.00	Each			
18	Providing & fixing P.V.C soil waste and vent pipes, single or double socketed, including pipe clip complete (excluding the cost of PVC fittings) 110mm dia	20.00	m			

	75mm dia	15.00	m			
19	Providing & fixing P.V.C plain bend 110mm dia	17.00	Each			
20	Providing & fixing P.V.C door bend	17.00	Each			
21	Size 1200x1200x1200mm, filled with brick bats including 100mm SW drain pipe X 1200mm long	1.00	Each			
22	Providing & fixing Electric water heater including necessary fittings 100 litres	4.00	Each			
23	Providing & fixing plastic tank including all accessories complete 2000 litre capacity	1.00	Each			
24	Providing & fixing c.p. brass mixers, 15mm	4.00	each			