

**Name of Work: Renovation of School Building at Tang Central school**

**Location :Tang Geog**

**Detail: BoQ**

Sl.No	Description	Qty	Unit	Rate in Figure	Rate in Words	Amount
1	Removing mortar from stones, cleaning stones and concrete articles, and arranging in stacks-In lime mortar	27.35	Sqm			
2	Providing & laying 20mm cement plaster-C.M 1:3 (rate should include all filling of holes and irregularities of building wall)	555.98	Sqm			
3	Taking out doors, windows and clerestory windows shutters <3sq.m (steel, wood) including stacking within 50m lead-window shutter	52.00	each			
4	Providing & fixing 35mm thick Panelled or glazed doors and windows Shutters etc. complete including hinges-MC	74.62	Sqm			
5	Providing & fixing M.S tower bolt (barrel type) with necessary screws etc. complete-150mm	104.00	each			
6	Providing & fixing M.S. handle with necessary screws etc. complete-150mm	104.00	each			
7	Providing & fixing M.S. hook-and-eye with necessary screws etc. complete-150mm	104.00	each			
8	Providing & applying white or colour washing-White washing with lime-new work-three coats	260.15	Sqm			
9	Traditional Bhutanese Paintings all complete(removing old paints by scraping and sand papering -(cornices, railing, bamboo mat, door and window openings)		L/sum			
	<b>Total Amount=</b>					