

Name of Work: Maintenance of Old BHU and Staff Quarter at Tang**Location :Tang Geog****Detail: BoQ**

SI.No	Description	Qty	Unit	Rate in Figure	Rate in words
Staff Quarter Maintenance work					
1	Demolishing cement concrete 1:3:6 & richer, including disposal of materials within 50m lead	0.67	Cum		
2	Dismantling of ekra wall in cement mortar 1:6 or richer including stacking useful materials & disposal of rubbish within 50m lead	23.60	Sqm		
3	Providing and laying in position plain cement concrete excluding the cost of centering and shuttering - All work upto plinth level.-1:3:6 (1 cement : 3 sand : 6 graded crushed rock 20mm nominal size)	1.86	Cum		
4	Providing & fixing 75mm thick split bamboo wall including grooving frames, 20mm plaster cement mortar 1:4 both sides (excluding cost of frame)	23.60	Sqm		
5	Removing and chipping mortar from stones, cleaning stones and concrete articles, and arranging in stacks -In cement mortar	2.34	Cum		
6	Providing & laying 20mm cement plaster-C.M 1:4	34.85	Sqm		
7	Providing & fixing joists, including hoisting, applying wood preservative on unexposed surfaces-Mc	0.18	Cum		
8	Providing & fixing Mixed Conifer Flooring including fixing with iron screws etc. complete, excluding the cost of frame-40mm thick, half-lapped	2.25	Sqm		
9	Surface preparation removing by scraping, sand papering, including scratch repairs of old paints-Dry oil bound distemper	180.00	Sqm		
10	Providing & applying one coat of primers-Metal work - synthetic red oxide primer	180.00	Sqm		
11	Providing and applying finishing coats- Red corrugal, ready mixed\on G.I. sheets, two coats on new work	180.00	Sqm		

12	Providing & applying white or colour washing-White washing with lime-new work-three coats	47.19	Sqm		
Maintenance of Old BHU					
13	Removing and chipping mortar from stones, cleaning stones and concrete articles, and arranging in stacks -In cement mortar	2.09	Cum		
14	Providing & laying 20mm cement plaster-C.M 1:4	41.82	Sqm		
15	Demolishing cement concrete 1:3:6 & richer, including disposal of materials within 50m lead	11.57	Cum		
16	Providing and laying in position plain cement concrete excluding the cost of centering and shuttering - All work upto plinth level.-1:3:6 (1 cement : 3 sand : 6 graded crushed rock 20mm nominal size)	12.71	Cum		
17	Providing & laying Random Rubble Masonry with hard stone in foundation & plinth-In cement mortar 1:4	1.52	Cum		
18	Constructing random rubble masonry open surface drain in cement mortar 1:6 including earth work in excavation, 100mm thick concrete base 1:5:10, 40 mm aggregate 25mm thick cement concrete 1:2:4, 12mm aggregate for filling haunches,including 20mm cement plaster with a floating coat of neat cement, disposal of surplus earth-100 x 200mm depth	25.00	m		
19	Surface preparation removing by scraping, sand papering, including scratch repairs of old paints-Dry oil bound distemper	268.90	Sqm		
20	Providing & applying one coat of primers-Metal work - synthetic red oxide primer	268.90	Sqm		
21	Providing and applying finishing coats- Red corrugal, ready mixed\on G.I. sheets, two coats on new work	268.90	Sqm		
Grand Total Amount =					

